

Schedule Installation

Available Install Actions

- **Pre-Upgrade**

- Establishes initial device connection.
- Records running software version.
- Records the running configuration and stores it in a file.
- Checks the state of all nodes on the system.
- Verifies server repository reachability.
- Records inactive, active, committed package list.

Optional Plugins:

- Records OSPF and ISIS neighbors.
- Sets ISIS set-overload-bit if ISIS is running.
- Records total number of BGP neighbors.
- Records total number of MPLS LDP neighbors.
- Records total number of PIM neighbors.
- Records total number of HSRP neighbors and states.
- Records total number of VRRP neighbors and states.

- **Install Add**

- Copies software packages to the device.

- **Activate**

- Activates packages on the device.

- **Post-Upgrade**

- Checks node status, standby role status, configuration failure, software package states, etc.
- Verifies error/tracebacks/core files.

- **Commit**

- Executes Install Commit on the device

Available Install Actions - Continue

- **ALL**
 - CSM Server will create Pre-Upgrade, Install Add, Activate, Post-Upgrade, and Commit installation actions with the successor depending on the predecessor. Until the predecessor has executed successfully, the successor will not run.
- **Remove**
 - Removes inactive packages on the device.
- **Deactivate**
 - Deactivates active packages on the device.

Schedule an Install

- Invoked from the Host Dashboard's Action menu.
- Select an install action. Multiple install actions may be selected at once.
- Depending on the selected install action, software packages can be selected from Server Repository, CCO, Inactive Packages, or Install History.
- If a dependency is selected, the scheduled installation will not proceed until the dependency is completed successfully. The dependency can only be specified when only one install action is selected (not available for batch installs or when multiple install actions are specified).
- Click the Calendar icon to change the scheduled time. By default, it is the current date and time.

Schedule Install > Region: Cisco Telecom West Coast > Host: ASR9K-PE1-R0 (ASR9K-PX-5.3.1)

Install Action

× Install Add

Select From



Server Repository



CCO

Software Packages

asr9k-px-5.3.1.CSCuu96153.pie
asr9k-px-5.3.1.CSCuw01521.pie
asr9k-px-5.3.1.CSCuu77478.pie

Server Repository: Terastream-tme(17220168195)

Scheduled Time

10/08/2015 10:52 AM



Dependency

None

Schedule

Cancel

Browse Server Repository

- Invoked by clicking the Server Repository icon on the Schedule Install page.
- Select a server repository.
- Use the Server Directory selector to navigate to the desired directory on the server repository. The software packages in the selected directory will be displayed in the dual list box.
- For Software upgrade, enter the target software release and click Auto Select. This will select packages from the Available Packages list box which match the device software packages.

Select Software Packages > Host: ASR9K-PE1-R0 (ASR9K-PX-5.3.1)

Server Repository

Terastream-tme(17220168195)

Server Directory

5.3.2.18l

Target Software Release

Software Upgrade Only (enter X.X.X format)

Auto Select

Available Packages - showing 19

Filter

asr9k-5.3.2.18l.SIT_IMAGE-V2.tar
asr9k-fpd-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-k9sec-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-mcast-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-mgbl-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-mini-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-optic-px.pie-5.3.2.18l.SIT_IMAGE
asr9k-px-5.3.2.18l.CSCuv39804-0.0.3.i.pie
asr9k-px-5.3.2.18l.CSCuv57878-0.0.3.i.pie
asr9k-px-5.3.2.18l.CSCuv60802-0.0.2.d.pie

≡ >

>

<

< ≡

Selected Packages - showing 0

Filter

Save

Cancel

© Cisco Systems, Inc. All rights reserved.

5

Browse CCO

- Invoked by clicking the CCO icon on the Schedule Install page.
- Use the Browse CCO button to navigate to the desired platform and release.
- Select the server repository where the downloaded files should be stored.
- If you are scheduling for a single host, the Hide Installed Packages checkbox will be shown and checked by default. CSM Server filters all installed packages (i.e. Active Packages) from the display list.
- If Hide Installed Packages checkbox is unchecked, the installed packages will be highlighted in green color.

Browse CCO ▾

▼

Optimal

×

Server Repository

FTP SERVER

Server Directory

↑

×

Posted Within a Week

Installed Packages

☐ Hide Installed Packages

ASR9K-PX-4.3.4 > SMUs 60

Service Packs 1

100 ▾ records per page

Search:

<input type="checkbox"/>	Posted Date ▾	SMU ID ▾	DDTS	Type	Description
<input type="checkbox"/>	08/13/2015	AA10041	CSCu184303	Optional	Huge Counters on Bundle-ether Sub-Interface
<input type="checkbox"/>	08/03/2015	AA10030	CSCuo31977	Optional	CPP Driver LOCKDOWN & LC reload with control w
<input type="checkbox"/>	06/25/2015	AA09949	CSCuu53372	Optional	Umbrella SMU for CSCug92264 and CSCut69575
<input type="checkbox"/>	06/11/2015	AA09903	CSCuq31566	Optional	telnetd crash when receiving malformed telnet pack
<input type="checkbox"/>	06/05/2015	AA09769	CSCue32438	Optional	Enhancement to support the ability to increase VQI
<input type="checkbox"/>	05/22/2015	AA09776	CSCut57910	Optional	MLACP standby bundle ipv4 cap in IM chain stuck
<input type="checkbox"/>	05/06/2015	AA09634	CSCus71103	Recommended	V2 power brick causes voltage alarm for IBV sensor
<input type="checkbox"/>	05/22/2015	AA09638	CSCus26923	Optional	traffic from SIP700 to 9000v is dropped when a link
<input type="checkbox"/>	05/21/2015	AA09386	CSCus80007	Optional	Umbrella DDTS for DHCPv6 issues

Click to Select

Browse Inactive Packages

- Invoked by clicking the Inactive Pkgs icon on the Schedule Install page.
- The Last Successful Retrieval text field displays the elapsed time since the software packages was last successfully retrieved.
- Click the Retrieve Latest Software icon to retrieve latest software if necessary.

Install Action: Activate



Host

ASR9K-PE1-R0

Last Successful Retrieval

11h 3m 15s ago



Target Software Release

5.1.3

Auto Select

Available Inactive-Packages - showing 75

Filter

asr9k-9000v-nV-px-5.1.3
asr9k-9000v-nV-px-5.3.1
asr9k-asr901-nV-px-5.1.3
asr9k-asr901-nV-px-5.3.1
asr9k-asr903-nV-px-5.1.3
asr9k-asr903-nV-px-5.3.1
asr9k-bng-px-5.1.3
asr9k-bng-px-5.3.1
asr9k-doc-px-5.1.0
asr9k-fpd-px-5.1.0



Selected Inactive-Packages - showing 6

Filter

asr9k-doc-px-5.1.3
asr9k-k9sec-px-5.1.3
asr9k-mcast-px-5.1.3
asr9k-mgbl-px-5.1.3
asr9k-mini-px-5.1.3
asr9k-optic-px-5.1.3

Save

Cancel

Browse Install History

- Invoked by clicking the Browse Install History icon on the Schedule Install page.
- Select the packages from one of the successful Install Add operations.

Select from Install History

X

Host

ASR9K-PE1-R0

100 records per page

Search:

Packages	Installed Time	Installed By
<input type="checkbox"/> 4_3_4_smu.tar	09/11/2015 12:57 AM	root
<input type="checkbox"/> asr9k-doc-px.pie-5.1.3	09/07/2015 10:29 AM	root
<input type="checkbox"/> asr9k-px-5.1.0.CSCut30136.pie asr9k-px-5.1.0.CSCul26794.pie asr9k-px-5.1.0.CSCul19600.pie	08/23/2015 08:46 PM	root
<input type="checkbox"/> XR510FCS.tar	08/10/2015 04:12 AM	root

Showing 1 to 51 of 51 entries

← Previous 1 Next →

Save

Cancel

Schedule Install – Prerequisite Checks

After clicking the Schedule button, CSM Server performs the following functions:

- It checks for missing pre-requisites on selected software packages.
- It determines whether selected software packages are on the server repository. If they are not, CSM Server prompts the user to download them.
- The scheduled install will not proceed at its scheduled time until the software packages are successfully downloaded and copied to the server repository.

Following pre-requisite(s) were not selected, but should be included. ×

asr9k-px-4.3.1.CSCui38382.pie - 431 C-SMU1
asr9k-px-4.3.1.CSCug87873.pie - Support TE link Extended Admin Group and higher SRLG scale
asr9k-px-4.3.1.CSCun74284.pie - qos_ea and qos_ma consume high CPU in 4.3
asr9k-px-4.3.1.CSCug88702.pie - Excessive Punt Flow Trap does not police bad actor traffic
asr9k-px-4.3.1.CSCuh09480.pie - IPv6 ND is broken when MLD is enabled on the interface.
asr9k-px-4.3.1.CSCuj55425.pie - Chkpt treats current Active node as a Stby node(chkpt_register fails)
asr9k-px-4.3.1.CSCuf77118.pie - Serial DS3 - stays up when looped in HDLC - down-when-looped configured
asr9k-px-4.3.1.CSCuh55354.pie - 4.3.1.CCO: ASR9K POS int with HDLS encap flap when oversubscribe
asr9k-px-4.3.1.CSCuh40754.pie - Umbrella SMU for CSCug17684, CSCug83539, CSCuh02594

[Include Pre-requisites](#) [Ignore](#) [Cancel](#)

Following files are missing on the server repository. Those that are identified as 'Downloadable' × can be downloaded from CCO. If there is an scheduled installation that depends on these files, it will not proceed until the files are successfully downloaded and copied to the server repository.

asr9k-px-4.3.1.CSCuj55425.pie (Downloadable) - Chkpt treats current Active node as a Stby node(chkpt_register fails)
asr9k-px-4.3.1.CSCug88702.pie (Downloadable) - Excessive Punt Flow Trap does not police bad actor traffic
asr9k-px-4.3.1.CSCuh40754.pie (Downloadable) - Umbrella SMU for CSCug17684, CSCug83539, CSCuh02594
asr9k-px-4.3.1.CSCuh55354.pie (Downloadable) - 4.3.1.CCO: ASR9K POS int with HDLS encap flap when oversubscribe
asr9k-px-4.3.1.CSCui38382.pie (Downloadable) - 431 C-SMU1
asr9k-px-4.3.1.CSCuf77118.pie (Downloadable) - Serial DS3 - stays up when looped in HDLC - down-when-looped configured
asr9k-px-4.3.1.CSCuh09480.pie (Downloadable) - IPv6 ND is broken when MLD is enabled on the interface.
asr9k-px-4.3.1.CSCul42259.pie (Downloadable) - XR520:BFD packets getting dropped at NPU in Asr9k for FLEX LSP/MPLS-TP
asr9k-px-4.3.1.CSCun74284.pie (Downloadable) - qos_ea and qos_ma consume high CPU in 4.3
asr9k-px-4.3.1.CSCut52232.pie (Downloadable) - Production SMU for SAM post Oct 2015.
asr9k-px-4.3.1.CSCug87873.pie (Downloadable) - Support TE link Extended Admin Group and higher SRLG scale

[Download](#) [Ignore](#) [Cancel](#)

Installation Dependency

- A dependency can be specified when creating a scheduled install. For example, Install Activate should not be performed unless Install Add is successful.
- If an installation failed, any scheduled install that has the failed installation as its dependency will not execute.
- When multiple install actions or 'ALL' is selected, CSM Server will create the dependency automatically.
- Deleting a scheduled install will also delete all of its dependencies.

Scheduled Time

10/08/2015 11:58 AM

Dependency

✓ None

Pre-Upgrade - 10/15/2015 10:30 AM

Install Add - 10/15/2015 10:30 AM

Activate - 10/15/2015 10:30 AM

Post-Upgrade - 10/15/2015 10:30 AM

Commit - 10/15/2015 10:30 AM

Scheduled 5

In Progress 0

Failed 0

Completed

10

records per page

Hostname	Install Action	Dependency
ASR9K-PE1-R0	Pre-Upgrade	
ASR9K-PE1-R0	Install Add	Another Installation
ASR9K-PE1-R0	Activate	Another Installation
ASR9K-PE1-R0	Post-Upgrade	Another Installation

Schedule Batch Installation

Schedule Batch Installs

- Invoked by clicking the Schedule Batch Installs icon on the home page or the Action button on the Install Dashboard page.
- Select a region of interest.
- Select a role and/or software version to further filter hosts. Multiple roles or software versions may be selected.
- All managed hosts belonging to the selected region, role, and software version role will be displayed.
- Use the dual list box to select multiple hosts for the same scheduled installation.
- Click the Calendar icon to change the scheduled time. By default, it is the current date and time.

Select Hosts

Region

Cisco Telecom West Coast

Role

Software Version

× asr9k-px 5.3.1

× asr9k-px 5.1.3

Available Hosts - showing 5

Filter

ASR9K (Alex)
ASR9K-PE1-R0
ASR9K-PE2-R1
ASR9K-PE3
ASR9K-PE5

Selected Hosts - showing 0

Filter

≡ >

>

<

< ≡

Schedule Batch Installs

Install Action

Select Desirable Install Actions

Scheduled Time

10/13/2015 10:05 AM

